

Land clearing creates a large volume of brush, saplings, limbs, logs, and vegetation that must be processed or removed before grading, fencing, construction, or landscaping can continue. **Land clearing debris removal with grapple truck** equipment allows bulky organic material to be loaded faster than traditional hand-loading methods.



Volusia Bobcat & Tree Service - DeLand provides bobcat and grapple truck services for residential, commercial, and contractor projects in DeLand and surrounding Volusia County communities. Call **(386) 243-5682** to discuss the site and the desired finished condition.



Debris From Selective and Complete Clearing

Selective clearing may produce vines, brush, small trees, branches, and isolated logs while preserving mature trees. Larger site-clearing projects may generate heavy trunk sections, root material, dense vegetation, and multiple debris piles. The hauling plan should match the volume [web design](#) and the next phase of work.

Bobcat Staging and Grapple Loading

Bobcat equipment can collect scattered material, move logs, and build organized piles where the grapple truck can reach them. The grapple then lifts the vegetation into the truck for hauling. This combination is effective when the debris is spread across acreage or located beyond the truck's direct reach.

Land Clearing Debris Removal Volusia County Contractors Need

Contractors may need debris removed before survey work, grading, concrete, utility installation, fencing, or equipment delivery. Timely hauling helps keep the project moving and prevents vegetation piles from blocking access. Scheduling can be coordinated around the clearing crew when the load area and material type are confirmed in advance.

Material Separation Matters

Keep vegetation separate from concrete, asphalt, roofing, treated wood, metal, household waste, and hazardous material. Mixed loads may require different disposal facilities and can change the price significantly. Dirt-heavy stumps and root balls should be identified before the estimate.

Site Access and Loading Conditions

The truck needs safe road access, room to position, and adequate overhead clearance. Soft ground, narrow entrances, steep grades, wet areas, and active construction traffic can affect the loading plan. Mark septic systems, wells, irrigation, and underground utilities before equipment enters the property.

Request Land Clearing Debris Hauling

For lot cleanup, brush hauling, log removal, and **land clearing debris removal Volusia County** projects, call **Volusia Bobcat & Tree Service - DeLand at (386) 243-5682**. Provide the acreage, pile sizes, access details, and project timeline for a useful estimate.